

SOGR - Babylon Station
Division of Labor
Bid Submission

| | Work Element | Contractor | | Force Account | |
|--|--|--|---------|---------------|---------|
| | | Furnish | Install | Furnish | Install |
| STRUCTURAL/ARCHITECTURAL | Mark-outs of LIRR utilities | | | x | x |
| | Relocate car markers | | | x | x |
| | Door cores | x | | | x |
| | Temporary fencing, protection, and MPT | x | x | | |
| | Demolish platforms and CMU walls | x | x | | |
| | New ASIMS platform | x | x | | |
| | Demolish and reconstruct platform stair | x | x | | |
| | Demolish and reconstruct canopy (including downspouts, gutter, support steel and canopy) | x | x | | |
| | Repair platform supports above viaduct structure | x | x | | |
| | Repair viaduct superstructure | x | x | | |
| | New stairs at east end of platform | x | x | | |
| | Expansion joints | x | x | | |
| | Tactile warning system | x | x | | |
| | Excavate and reconstruct for escalators and elevators | x | x | | |
| | Refurbish existing elevator machine room (EMR) | x | x | | |
| | New elevator machine room (EMR) including the structure, insulation, cladding, roofing, floor drainage, door/hardware, and foundation. | x | x | | |
| | Construct new building at plaza level to accommodate new boiler room | x | x | | |
| | Construct new boiler room and all required equipment to support the ASIMS | x | x | | |
| | Construct electrical room, new security equipment closet, new IT equipment closet, and the new elevator machine room | x | x | | |
| | Eliminate existing taxi stand | x | x | | |
| | Construct new structure for concessionaire | x | x | | |
| | Construct new structure for a security equipment closet and the MTA Police Department kiosk | x | x | | |
| | Provide wheelhouse at each platform: one for MoE Department and another for Transportation Department | x | x | | |
| | Rubbing board | x | x | | |
| | Substructure repair for hammerhead piers (crack, spall, delamination, etc) | x | x | | |
| | Waterproofing | x | x | | |
| | Elevator framing | x | x | | |
| | Misc. site works demolition | x | x | | |
| | Aluminum storefront system (at stairs and waiting rooms) | x | x | | |
| | CMU partitions | x | x | | |
| | Demolish platform existing waiting rooms | x | x | | |
| | Platform waiting rooms | x | x | | |
| | Doors, frames and hardware (including electric mortise locks) | x | x | | |
| | Metal panel enclosure for conduit raceway | x | x | | |
| | New stair guardrails and handrails | x | x | | |
| | Viaduct guardrailing | x | x | | |
| | End of platform guardrail, gates and employee ladder | x | x | | |
| | Replace signage throughout station | x | x | | |
| | Bird deterrent | x | x | | |
| | Elevator enclosures (at existing and new) | x | x | | |
| | Remove and replace bike racks | x | x | | |
| | MTA Arts and Design - sculptures, glazing, railings and/or mosaic tiles | x | x | | |
| | Landscaping and hardscapes in plaza area | x | x | | |
| | Concrete/paving in plaza area (curb cuts/ADA tactile and walkways) | x | x | | |
| | MECHANICAL | Storm drain piping for canopies and connect to storm utility | x | x | |
| HVAC for new ASIMS | | x | x | | |
| Power washing dry line | | x | x | | |
| HVAC system for waiting rooms | | x | x | | |
| Plumbing for waiting rooms | | x | x | | |
| HVAC in elevator machine room | | x | x | | |
| Plumbing at elevator machine room | | x | x | | |
| Plumbing at elevator pit | | x | x | | |
| Plumbing in boiler room building, including floor drain and roof drain | | x | x | | |
| HVAC system in boiler room building | | x | x | | |
| Plumbing in new vendor structure | | x | x | | |
| ASIMS equipment in Boiler Room | | x | x | | |
| HVAC in new vendor structure | | x | x | | |
| Plumbing in new MTA PD kiosk | | x | x | | |

| | Work Element | Contractor | | Force Account | |
|--|---|------------|---------|---------------|---------|
| | | Furnish | Install | Furnish | Install |
| | HVAC in new MTA PD kiosk | x | x | | |
| | Connections to existing | x | | | x |
| | Inspections, testing, and commissioning | | | | x |
| | | | | | |

| | Work Element | Contractor | | Force Account | |
|-------------------------|--|------------|---------|---------------|--------------|
| | | Furnish | Install | Furnish | Install |
| ELECTRICAL | Mark-outs of LIRR utilities | | | x | x |
| | Demolition of all existing electrical components (light poles, panels, lights, etc.) on platforms and under viaduct area | | | x | x |
| | Demolition of existing LIRR owned electrical service equipment | | | x | x |
| | Disconnect existing electrical feeds | | | x | x |
| | Electrical circuitry at platform | x | x | | |
| | Electrical circuitry at plaza | x | x | | |
| | New platform and canopy lighting (including conduit and wiring) | x | | | x |
| | All underpass work and lighting (which is currently owned and maintained by LIRR) | x | | | x |
| | Replacement of all existing panels and associated equipment (conduits, boxes, cables) in poor condition | x | | | x |
| | Lighting fixtures at platform | x | x | | |
| | Lighting fixtures at plaza | x | x | | |
| | Lighting switches | x | x | | |
| | Pull boxes on outside of existing electrical room | x | x | | |
| | Conduit and work inside existing electrical room | x | | | x |
| | Electrical service transformer and equipment (install at new location separate from existing) | x | x | | |
| | Ductbank (install at new location separate from existing) | x | x | | |
| | Complete run and termination of demarc box or MH | x | | | x |
| | All tie-ins from new electrical room to any existing LIRR owned room, building, equipment, or component | x | | | x |
| | Panelboards | x | x | | |
| | Circuit breakers | x | x | | |
| | Disconnect switches | x | x | | |
| | Blue light system at each end of platform | x | | | x |
| | Automatic transfer switch | x | x | | |
| | Receptacles | x | x | | |
| | Power to elevators | x | x | | |
| | Power to escalators | x | x | | |
| | Elevator machine room electrical feeds and panels | x | x | | |
| | Boiler room electrical feeds and panels | x | x | | |
| | Advertisement board conduits and cables | x | x | | |
| | Advertisement boards | | x | x | |
| | New electrical service | x | x | | |
| | Temporary lighting and power | x | x | | |
| | Inspections, testing, and commissioning | | x (New) | | x (Existing) |
| COMMUNICATIONS | Mark-outs of LIRR utilities | | | x | x |
| | Review and comment on all communications designs | | | x | x |
| | Final terminations at existing communications infrastructure | | | x | x |
| | Furnish and install CCTV cameras for the interior of the elevator | x | x | | |
| | Travel cable, emergency phone, media converters, SFP modules, and elevator camera (CCTV) | x | x | | |
| | Furnish and install CCTV cameras for the platform and street level | | | x | x |
| | Access card readers | | | x | x |
| | Remove and reinstall communications system conduits, cables and devices attached to the platform/canopy section to be replaced | | | x | x |
| | Conduits and cables for communications systems (CCTV, Help Points, etc.) | | | x | x |
| | Coordinate support with telephone company for telephone upgrade | x | x | | |
| | Intercom phone connection from the elevator to EMR. Electrical service to be provided for the Telecommunications Device for the Deaf (TDD) and ADA phone illuminated signs | x | x | | |
| | Elevator intercom phone connection from the EMR to COMM room/enclosure | x | x | | |
| | Remove and reinstall two weatherproof help points emergency/information kiosks and supporting conduit, pull boxes, wiring and fiber optics | | | x | x |
| | Remove and install AVPS screens | | | x | x |
| | Inspections, testing, and commissioning | | | | x |
| VERTICAL TRANSPORTATION | Demolish existing elevator cab | x | x | | |
| | Rehabilitate existing elevators | x | x | | |
| | New elevators | x | x | | |
| | Demolish existing escalators | x | x | | |
| | New escalators | x | x | | |
| | Inspections, testing, commissioning, and 3rd Party Testing | | x | | |
| | Mark-outs of LIRR utilities. | | | x | x |

| | Work Element | Contractor | | Force Account | |
|----------------|---|------------|---------|---------------|---------|
| | | Furnish | Install | Furnish | Install |
| SIGNAL | Remove PTC for track resurfacing | | | x | x |
| | Perform signal cable relocation or protection as required | | | x | x |
| TRANSPORTATION | Flagging support for work on or about the tracks | | | x | x |
| FIRE ALARM | Fire alarm system components and associated wiring and conduit (LIRR Fire Alarm Vendor to perform this work) | x | x | | |
| | Inspection, testing, and commisioning | | x | | |
| MISCELLANEOUS | Remove and replace existing salt boxes, trash receptacles, and benches as required on the platforms and areas of work | | | x | x |
| | Asbestos and/or lead abatement | x | x | | |
| TRACK | Resurfacing of tracks | | | x | x |